

OM
OR
CR
Price Schedule

Name of work:Electrical Renovation work at Boys Hostel no 2 at NIT Silchar
Time of completion:60 days

ELECTRICAL					
Sl no	Item description	Unit	Qty.	Rate in Rs and in words	Amount in Rs and in words
1	POINT WIRING (IN PVC CONDUIT)				
	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.				
a.	Group A	Each	163.00		
b.	Group B	Each	206.00		
c.	Group C	Each	183.00		
2	Wiring for twin control light point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface /recessed medium class PVC conduit, 2 way piano type switch,phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required	point	8.00		
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	Mtr	40.00		
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	580.00		
	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtr	150.00		
	4 X 10 sq. mm + 2 X 6 sq. mm earth wire	Mtr	350.00		
4	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
	5/6 A switch	Each	848.00		
	2 way 5/6 A switch	Each	8.00		
	15/16 A switch	Each	10.00		
	3 pin 5/6 A socket outlet	Each	248.00		

OM
OR
CR

	6 pin 15/16 A socket outlet	Each	10.00		
5	Supplying and fixing two module stepped type electronic fan regulator on the existing switch box including connections as required.	Each	160.00		
6	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	Each	400.00		
7	Supplying and fixing brass batten/ angle holder including connections etc. as required.	Each	200.00		
8	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube etc., including supplying and fixing ball and socket arrangement, 2 Nos. down rods of 20 mm dia X 1.6 mm thick steel conduit upto 30 cm length, painting and wiring the down rods and connections with 1.5 sq. mm FRLS PVC sulated, copper conductor, single core cable and earthing etc. as required	Each	600.00		
9	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required Upto 450 mm sweep	Each	15.00		
10	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as	Each			
	8 way, Double door	Each	1.00		
14	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required				
	Single pole	Each	160.00		
	Single pole and neutral	Each	10.00		
	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 4 way (4 + 12), Double door	Each	13.00		

OM
OR
CR

NON DSR rates					
20	Supply of following size LED lights complete with all accessories as required.				
a	18/20 watt Surface LED tube light complete all accessories.	Each	400		
	9 watt Surface LED bulb complete all accessories.	Each	200		
21	Supplying of 2.5 mfd capacitor including connection in the existing ceiling fan complete	Each	180		
22	Supply of following sizes of single phase 240 volts heavy duty exhaust fan complete with including all accessories as required. 450mm dia.	Each	18		
31	Supplying with fitting and fixing 4P 10 KA 240/415V 50Hz MCB of the following capacity complete with making necessary connection as approved, specified and directed by the deptt.C Series (ABB, Schneider MG, legrand, Hager make)100 Amps	Each	13		

Total Rs

Rupeesonly

Signature of the agency